



4550 Post Oak Place, Suite 202
 Houston, Texas 77027
 Phone: (713) 623-6900 * Fax: (713) 623-6905
 Web: www.qualitybit.com
 E-mail: quality@qualitybit.com

Rig 7 Inventory Summary

(Updated 08-16-08; Note - Inventory Subject to Change)

Unit/Hoist:	2003 Gefco Speedstar 30KDH, 40,000 Lb. Hoist & 25,000 Lb. Pull Down, w/ Single Pipe Loader.
Mast:	Free Standing 35' Tall, 60,000 Lb Load Rated
Carrier:	Petterbuilt 6 x 4 Tandem Axle, 66,000 GVW, w/Caterpillar C-15 Diesel Engine , 550 HP, w/ 150 Gal. Fuel Tank, Cotta GR16A Gear Box, (4) Hydraulic Leveling Jacks
Substructure:	5'H x 10'W x 20'L Working Platform Ramp Type
Blocks:	McKissick 50 Ton, M/N MDZ051ZM,
Jib Winch:	Single Line 20,000 Lb Hoist, Double Line 40,000 Lb Hoist
Coring Winch:	Longyear Hydraulic Winch Rated @ 3,352 Lb on Bare Drum
Casing Table:	Under Main Table will Handle Up To 9 5/8" Casing
Breakout Table:	Handles Casing To 16" with Sliding Wrench for Holding Drill Rod
Breakout Wrench:	60" Pipearm/Wrench w/ 8" Pipe-jaw Attached To Breakout Cylinder
Top Head:	Eaton 3" ID, 127 RPM @5,833 ft/lbs. of Torque
Compressor:	Sullair 1000 CFM @ 350 PSI., Unit Mounted
Injection Pump:	Water/Foam Injection w/ Variable Speed Hydraulic Control for Rated Output up to 25 GPM and 700 PSI w/ Flow Meter
Mud Pump:	CLM 7 1/2" x 10" DHPA Hydraulic Duplex Pump
Pipe Spinner:	(1) Mannesman Rexroth 4 1/2" x 3 1/2",
Ancillary Equipment:	Pipe Trailer - Tool Box Center Cat Walk, 40'L Tandem Axle, Doghouse.
Tubulars:	Drill Rod - 77 Jts. - 3 1/2" Drill Rod w/ 2 7/8" IF BxP Connections,